

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20226-00-00
Spot: SESESE Sec/Twnshp/Rge: 15-23S-4W
330 feet from S Section Line, 440 feet from E Section Line
Lease Name: NELSON Well #: 1
County: RENO Total Vertical Depth: 3406 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N STE1010D
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3405	816	100 SX
SURF	10.75	210		250 SX
T1	3	3336		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2012 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: _____

Proposed AS DIRECTED BY KCC.
Plugging
Method:

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/24/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

(10/23/12) SET CIBP @ 3290' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 816' PULLED CASING TO 619' SPOTTED 35 SX CEMENT. PULLED REST OF CASING OUT HOLE. 10-24-12 TAGGED TOP CEMENT @ 349'. ON 10-24-12, RAN TUBING INTO TO 312' CIRCULATED TO SURFACE WITH 225 SX CEMENT. 10-25-12 FELL BACK 15' ADDED 4 MORE SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3374	3378		
3364	3368		
3351	3355		
3348	3356		

RECEIVED
NOV 06 2012
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND. 60/40 4% POS MIX.

Plugged through: CSG

District: 02

Signed BJ Hope
12/12/12 (TECHNICIAN)