

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20393-00-00
Spot: NWNENW Sec/Twnshp/Rge: 20-15S-12W
330 feet from N Section Line, 1650 feet from W Section Line
Lease Name: REIF Well #: 2
County: RUSSELL Total Vertical Depth: 3325 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3320		100 SX
SURF	8.625	250		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2012 8:45 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN WEINHOLD Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 12 sx gel Perforations: 350', 820' and 1500'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2012 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3287' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 1500' and pumped 75 sx cement.
Pulled tubing to 800' and pumped 120 sx cement.
Cement circulated.
POOH and hooked up to 5 1/2" casing. Pumped 30 sx cement @ 250 psi. Shut in.
Hooked up to braden head and pumped 15 sx cement @ 200 psi.

GPS: 38.73947, -098.68564

Perfs:

Top	Bot	Thru	Comments
3320	3320		
3049	3056		

Remarks: QUALITY CEMENTING TICKET # 6136

Plugged through: TBG

RECEIVED
NOV 07 2012
KCC WICHITA

District: 04

Signed Ray A Dinkel
11/09/12 (TECHNICIAN) CM

NOV 02 2012