

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20859-00-00
Spot: SWSWSES Sec/Twnshp/Rge: 29-20S-34W
95 feet from S Section Line, 3944 feet from E Section Line
Lease Name: JAMES-CRIST Well #: 1
County: SCOTT Total Vertical Depth: 5052 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		2188		CMT TO SURFACE
PROD	5.5	5046	0	WITH 220 SX CMT
SURF	8.625	219		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2012 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GLENN Company: PALOMINO Phone: (316) 799-1000

Proposed Plugging Method: PUMP 200#HULLS & 30 SX CMT. MUD SPACER TO 2250'. CMT TO SURFACE FROM 2250'. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2012 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT WITH 200# HULLS FROM 4584' TO 4280'. PUMP SPACER FROM 4280' TO 2400'. PUMP 260 SX CMT FROM 2400' TO 0'. PRESSURE TO 400#. HOLDING. PUMP 10 SX CMT DOWN ANNULUS TO 250#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4574	4584		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

RECEIVED
NOV 27 2012

KCC WICHITA

District: 01

Signed

Ken Jehlik
11/26/12

(TECHNICIAN)

RECEIVED

NOV 20 2012

KCC DODGE CITY

Handwritten mark