

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-01328-00-00  
Spot: NWSEWNE Sec/Twnshp/Rge: 6-24S-5E  
977 feet from N Section Line, 3492 feet from W Section Line  
Lease Name: CLAASSEN Well #: 1  
County: BUTLER Total Vertical Depth: 2458 feet

Operator License No.: 7228  
Op Name: BRICKLEY, DONALD DBA D & J INVES  
Address: 128 N ALLEGHANY PO BOX 107  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2438	744	75 SX
SURF	7	190		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2012 9:00 AM

Plug Co. License No.: 7228 Plug Co. Name: BRICKLEY, DONALD DBA D & J INVESTMENTS

Proposal Rcvd. from: AJS SERVICES Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/19/2012 9:00 AM

KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

3/15 RAN 2" TUBING TO 2442' AND SPOTTED 25 SX OF 60 X 40>4% GEL. PULLED TUBING. CORNISH WIRELINE PERFORATED CASING AT 250'. TIED ONTO CASING AND ESTABLISHED CIRCULATION. BEGAN PUMPING CEMENT AND LOST CIRCULATION, LET SET 15 MINUTES, BEGAN PUMPING AGAIN, LOST CIRCULATION. TOTAL CEMENT PUMPED ON TOP PLUG - 200 SX. DECIDED TO LET CEMENT SET UP OVER NIGHT AND RETURN TO FINISH TOMORROW. CONSOLIDATED TICKET #36080. 3/16 - RAN 2" TUBING TO 330' AND STACKED OUT. PUMPED CEMENT AND UNTIL CASING STOOD FULL. CEMENT DID NOT CIRCULATE UP ANNULUS. PULLED TUBING. RAN 2" DOWN THE ANNULUS TO 190' AND STACKED OUT. PUMPED CEMENT UNTIL BULK TRUCK RAN OUT. AFTER SECOND BULK TRUCK ARRIVED, TOPPED OFF BOTH CASING AND ANNULUS FOR A TOTAL OF 175 SX. CONSOLIDATED TICKET #34266. BOTTOM PLUG = 25 SX. TOP PLUG = 375 SX.

RECEIVED  
NOV 14 2012  
KCC WICHITA

Remarks: FIRST TOP PLUG MUST HAVE FALLEN BUT NOT BEFORE PLUGGING OFF THE HOLES SHOT IN THE CASING.

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)