

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21083-00-00  
Spot: NWSENWSE Sec/Twnshp/Rge: 28-14S-19W  
1657 feet from S Section Line, 1761 feet from E Section Line  
Lease Name: SUNLEY-MOSER Well #: 1  
County: ELLIS Total Vertical Depth: 3738 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3733		125 SX
SURF	8.625	215		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2012 11:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Squeezed @ 720'-735' w/400 sx, 2770' w/150 sx, 2554' - 2650' w/250 sx.  
Casing leaks at 2554' - 2650'. CIBP at 3495'.  
Cemented in packer at 2358'.  
Perforated ARB at 3733' - 3741'; OH

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/06/2012 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 2327' and pumped 100 sx cement w/350 # hulls.  
Pulled tubing to 1000' and pumped 70 sx cement to circulate cement to the pit area.  
Pulled tubing, rigged to 4 1/2" casing and pumped 10 sx cement to pressure with 100 psi. Shut in pressure 100 psi.  
Rigged to 8 5/8" casing and pumped 5 sx cement to pressue with 100 psi. Shut in pressure 100 psi.

GPS: 38.80279 -099.43551

Perfs:

RECEIVED  
NOV 13 2012  
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING INC.

Plugged through: TBG

District: 04

Signed [Signature]  
12/12/12 (TECHNICIAN)

CM