

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22660-00-00  
Spot: E2NENWSW Sec/Twnshp/Rge: 10-6S-22W  
2310 feet from S Section Line, 1210 feet from W Section Line  
Lease Name: RUSH TRUST Well #: 4  
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 300 W DOUGLAS AVE, STE 410  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3829		125 SX
SURF	8.625	336		215 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2012 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TERRY PIESKER Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-4363

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls and 9 sx gel.  
Perforated @ 1919' w/400 sx cement.  
Perforations: 3650' - 3654'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2012 11:32 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' and pumped 9 sx gel followed by 75 sx cement w/100# hulls.  
Pulled tubing to 2065' and pumped 100 sx cement w/200# hulls.  
Pulled tubing to 1037' and pumped 134 sx cement w/100 # hulls.  
Pulled tubing out of hole. Topped off with 18 sx cement. Hole standing full.  
Back side full of cement.

GPS: 39.54556 -099.76530

Perfs:


Top	Bot	Thru	Comments
3650	3654		

RECEIVED  
NOV 13 2012  
KCC WICHITA

Remarks: EXPRESS WELL SERVICE W/TERRY PIESKER ON JOB

Plugged through: TBG

District: 04

Signed:   
(TECHNICIAN)

CM

NOV 05 2012