

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20745-00-00
Spot: N2SESENE Sec/Twnshp/Rge: 11-29S-1W
3120 feet from S Section Line, 330 feet from E Section Line
Lease Name: KILLION-HILL - UNIT A Well #: 2
County: SEDGWICK Total Vertical Depth: 3698 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3680		
PROD	4.5	3683	2481	175 SX
SURF	9.625	203		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2012 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: According to the rules and regulations of the KCC.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 09/19/2012 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

SANDED BACK TO 2500'. WORKED PIPE. DUMP BAILED 2 SAX CEMENT ON TOP OF SAND. SHOT 4 1/2" CASING OFF AT 2481' AND PULLED. RAN PIPE TO 265' AND CIRCULATED 195 SAX 60/40 4% GEL TO SURFACE. JOB COMPLETE. TOTAL CEMENT 197 SX.

Perfs:

Top	Bot	Thru	Comments
3675	3680		
3668	3671		
3662	3665		

RECEIVED
NOV 14 2012

Remarks:

Plugged through: CSG

District: 02

Signed Jeff Klock DISTRICT SUPERVISOR
(TECHNICIAN)