

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-10019-00-01 2001  
Spot: NESWNWE Sec/Twnshp/Rge: 2-33S-30W  
4622 feet from S Section Line, 2022 feet from E Section Line  
Lease Name: STEVENS (MORROW) UNIT Well #: 202  
County: MEADE Total Vertical Depth: 5890 feet

Operator License No.: 32198  
Op Name: PETROSANTANDER (USA) INC.  
Address: 6363 WOODWAY DR STE350  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		5619		
PROD	5.5	5890	2500	WITH 200 SX CMT
RBP		5573		
SURF	8.625	1636		WITH 750 SX CMT

Well Type: EOR UIC Docket No: E27792.11 Date/Time to Plug: 11/09/2012 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GORDON AUSTIN Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: SET CIBP @ 5573' WITH 2 SX CMT. PLUG AT 1680' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: NONE  
Date/Time Plugging Completed: 11/09/2012 5:30 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

RETRIEVABLE BRIDGE PLUG AT 5573'. CASING LEAKS WERE SQUEEZED FROM 2930' TO 3385'. WHILE DRILLING OUT THE CMT, CIRCULATION WAS LOST & DECISION WAS MADE TO PLUG WELL. SHOT OFF CSING AT 2500'. RUN TBG TO 1680' PUMP 15 SX GEL & 50 SX COMMON CMT W/4% CC. NO HULLS. NO CIRCULATION. RUN TBG TO 1680 PUMP 50 SX COMMON CMT W/4% CC & 400# HULLS. NO CIRCULATION. TAG TOC @ 1852'. RUN TBG TO 1851' & PUMP 50 SX COMMON CMT. HOLE CIRCULATED. PUMP 50 SX CMT AT 610'. PUMP 15 SX CMT @ 40'.

Perfs:

Top	Bot	Thru	Comments
5649	5707		

RECEIVED  
NOV 27 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: NOV MIT LTR SENT\*\* USED COMMON & 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED  
NOV 20 2012  
KCC DODGE CITY

Signed

Daniel Bernasconi  
11/29/12 (TECHNICIAN)  
\* cc to KCC 11/27/12