

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-23769-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 2-22S-10E
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: D & S (DEMALORIE SOWDER) Well #: 99
County: GREENWOOD Total Vertical Depth: 2625 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2619		75 SX
SURF	8.625	207		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2012 2:30 PM

Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN G. STOUT Company: _____ Phone: (316) 640-9072

Proposed Plugging Method: SET A 50 FT CEMENT PLUG ON BOTTOM. SHOOT OFF CASING AT 1000'. SET A 50FT CEMENT PLUG. PULL TUBING TO 150' AND CEMENT TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed: 11/26/2012 4:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

sand off perfs. Ran tubing toto 2600' pumped 10 sxs cement, pulled tubing out, shot casing @ 1000' pumped 20 sxs cement, pulled tubinto 250' circ. Cement to surface gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2608	2612		

RECEIVED

DEC 03 2012

KCC Chanute Dist. #3

mtt

RECEIVED

DEC 05 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern (TECHNICIAN)
12/05/12