

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-10025-00-02 0082  
Spot: SENWSENE Sec/Twnshp/Rge: 35-32S-30W  
3304 feet from S Section Line, 829 feet from E Section Line  
Lease Name: STEVENS (MORROW) UNIT Well #: 3508  
County: MEADE Total Vertical Depth: 5795 feet

Operator License No.: 32198  
Op Name: PETROSANTANDER (USA) INC.  
Address: 6363 WOODWAY DR STE350  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5240		WITH 2 SX CMT
CIBP		5700		
PROD	5.5	5792	1713	WITH 100 SX CMT
SURF	8.625	1614		WITH 850 SX CMT

Well Type: (EOR) UIC Docket No: E27792.13 Date/Time to Plug: 10/15/2012 10:30 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GORDON AUSTIN Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: SET CIBP @ 5590' WITH 2 SX CMT. PLUG AT 1650' WITH 15 SX GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE  
Date/Time Plugging Completed: 10/15/2012 12:30 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SET CIBP @ 5240' WITH 2 SX CMT. 1ST PLUG AT 1658' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 585' WITH 50 SX CMT. 3RD PLUG AT 65' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5658	5672		

RECEIVED  
NOV 09 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed: Daniel Bernasconi (TECHNICIAN)  
11/26/12

RECEIVED

NOV - 5 2012

KCC DISTRICT OFFICE