

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20741-00-01 0801
Spot: SWSESWNE Sec/Twnshp/Rge: 35-32S-30W
2958 feet from S Section Line, 1689 feet from E Section Line
Lease Name: STEVENS (MORROW) UNIT Well #: SMU 3507
County: MEADE Total Vertical Depth: 6250 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY DR STE350
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5570		WITH 2 SX CMT
CIBP		5700		
CIBP		6110		
CIBP		6249		
PROD	4.5	6249	0	WITH 305 SX CMT
SURF	8.625	1551	0	WITH 735 SX CMT

Well Type: EOR UIC Docket No: E27792.12 Date/Time to Plug: 10/15/2012 10:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GORDON AUSTIN Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: SET CIBP @ 5590' WITH 2 SX CMT. PERFORATE @ 1590' CIRCULATE TO SURFACE WITH 450 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE
Date/Time Plugging Completed: 10/15/2012 1:30 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SET CIBP @ 5570' WITH 2 SX CMT. PERFORATE @ 1590' & PUMPED 400 SX CMT. CMT CIRCULATED. TOOH W/TBG PUMPED 15 SX CMT. HOLE STOOD FULL.

Perfs:

Top	Bot	Thru	Comments
6180	6186		
5703	5716		
5637	5680		

RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV MIT LTR** USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED OIL WELL SERVICES.

Plugged through: TBG

District: 01

RECEIVED
NOV 20 2012
KCC DODGE CITY

Signed

Daniel Bernasconi
11/28/12 (TECHNICIAN)
cc to UIC 11/27/12

PLUG