

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22830-00-00
Spot: S2NWSESE Sec/Twnshp/Rge: 21-33S-11W
690 feet from S Section Line, 981 feet from E Section Line
Lease Name: FORESTER Well #: 2
County: BARBER Total Vertical Depth: 4700 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4495		WITH 2 SX CMT
PROD	4.5	4699	3890	WITH 125 SX CMT
SURF	8.625	267		WITH 215 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/13/2012 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4495' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2012 2:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4495' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 620' WITH GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4565	4569		
4545	4569		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Stephen P Pfeifer
(TECHNICIAN)

RECEIVED

NOV 19 2012

KCC DODGE CITY

RECEIVED
DEC 03 2012
KCC WICHITA

Handwritten initials