

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21287-00-00
Spot: W2W2 Sec/Twnshp/Rge: 22-32S-19W
2640 feet from S Section Line, 4620 feet from E Section Line
Lease Name: RICH C Well #: 6
County: COMANCHE Total Vertical Depth: 5910 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4910		WITH 2 SX CMT
COND	13.375	240		WITH 250 SX CMT
PROD	4.5	5418	4565	WITH 210 SX CMT
SURF	8.625	758		WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/20/2012 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4900' WITH 2 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 790' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT. PRESSURE TEST 13 3/8" X 8 5/8" ANNULUS WITH CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 11/20/2012 4:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4910' WITH 2 SX CMT. 1ST PLUG AT 1010' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 795' WITH 50 SX CMT. 3RD PLUG AT 306' WITH 40 SX CMT. 4TH PLUG AT 61' WITH 30 SX CMT. COULDN'T TIE IN TO PRESSURE TEST 13 3/8" X 8 5/8" ANNULUS WITH CMT.

Perfs:

Top	Bot	Thru	Comments
5164	5276		
5018	5025		
4963	4968		

RECEIVED
DEC 03 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
NOV 29 2012
KCC DODGE CITY

Signed

Richard M. Lacey
12/11/12 (TECHNICIAN)