

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20904-00-00  
Spot: NENW Sec/Twnshp/Rge: 14-23S-17W  
4646 feet from S Section Line, 3344 feet from E Section Line  
Lease Name: WYMAN Well #: 1  
County: PAWNEE Total Vertical Depth: 4240 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4060		WITH 2 SX CMT
PROD	4.5	4239	2091	WITH 150 SX CMT
SURF	8.625	324		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/03/2012 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4060' WITH 2 SX CMT. PLUG AT 1260' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/03/2012 11:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4060' & 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1267' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 371' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 34 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4130	4134		
4110	4127		

RECEIVED  
DEC 06 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard M. Lacey  
12/4/12 (TECHNICIAN)

RECEIVED  
DEC - 4 2012  
KCC DODGE CITY