

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22305-00-00
Spot: SWNESWNE Sec/Twnshp/Rge: 3-11S-24W
3460 feet from S Section Line, 1820 feet from E Section Line
Lease Name: GEYER Well #: 3
County: TREGO Total Vertical Depth: 3958 feet

Operator License No.: 33657
Op Name: OHIO KENTUCKY OIL CORPORATION
Address: THE WILLIAM M GRIFFITH BUILDING
LEXINGTON, KY 40503

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3942		150 sx
SURF	8.625	209		150 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2012 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: _____ Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/250 # hulls and 12 sx gel.
Port Collar at 1961' with 350 sx cement. Cement did not circulated. Perforation at 850'. CWC 200 sx.
Perforations at 3732' - 3749'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2012 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 3707' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 2000' and pumped 200 sx cement w/100 # hulls. Good circulation of cement.
Pulled tubing out. Topped off with 20 sx cement. Hole standing full.
Tied on to back side. Hole full. Shut in pressure 200 psi.
GPS: 39.12674 -099.96843

RECEIVED
NOV 29 2012
KCC WICHITA

Remarks: SWIFT CEMENT TICKET # 22895

Plugged through: TBG

District: 04

Signed  (TECHNICIAN) CM
11/13/12

NOV 13 2012