

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-30378-00-00  
Spot: NENWSENE Sec/Twnshp/Rge: 25-32S-4E  
3657 feet from S Section Line, 981 feet from E Section Line  
Lease Name: GANN Well #: 1  
County: COWLEY Total Vertical Depth: 3125 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	660		
PROD	0	0		0 SX
SURF	0	0		0 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: ALBERT COOPER Company: ALBERT COOPER/COOPER SERVIC Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS / PERFORATE @ 250', CEMENT FROM 660'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/05/2012 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/BIT & TBG CIRCULATING VARIOUS BRIDGES FROM 0'-660'. 11-5-2012, RIH ON WIRELINE, SHOT SQUEEZE HOLES (2 HOLES) @ 250'-250'-1/2". RIH W/TBG @ 570', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 250 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED ON BOTH STRINGS. PLUG DOWN 2:00 PM 11-5-2012. COPELAND ACID CEMENT TICKET #38119. 11-9-2012, TAGGED CEMENT @ 65', TOPPED WELL BACK TO SURFACE W/10 SXS.

Perfs:

RECEIVED  
DEC 04 2012  
KCC WICHITA

Remarks: COMPLIANCE / COMPLAINT

Plugged through: TBG

District: 02

Signed [Signature]  
12/02/12 (TECHNICIAN)

✓ SK