

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21905-00-00
Spot: SESENW Sec/Twnshp/Rge: 35-18S-28W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: SHAPLAND LIVING TRUSTS Well #: 1
County: LANE Total Vertical Depth: 4356 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: PO BOX 27710
DENVER, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1580		WITH 150 SX CMT
PROD	5.5	4356	0	WITH 150 SX CMT
SURF	8.625	308		WITH 210 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2012 10:00 AM

Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING Phone: (785) 737-3242

Proposed Plugging Method: RUN TBG TO 3630' & SPOT 30 SX CMT & 100# HULLS. PULL TBG TO 2140' & MIX UNTIL CIRCULATES. PULL TBG & TOP OFF. TIED ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/20/2012 10:00 AM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****LEFT 20 JOINTS & 24 RODS IN HOLE. COULDN'T GET BELOW 3630.**** 1ST PLUG RUN TBG IN TO 3610' & PUMP 30 SX CMT & 100# HULLS. 2ND PLUG PULL TBG TO 2140' & PUMP 200 SX CMT & 400# HULLS. CMT CIRCULATED. 3RD PUG PULL TBG & TOP OFF WITH 20 SX CMT. TIE ONTO BACKSIDE & PUMP 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4263	4268		

RECEIVED
DEC 07 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

NOV 30 2012

KCC DODGE CITY

Signed

Michael Maier
12/10/12

(TECHNICIAN)

BWD