

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-21139;00-01 0001  
Spot: SESWNWSE Sec/Twnshp/Rge: 21-9S-26W  
1480 feet from S Section Line, 2240 feet from E Section Line  
Lease Name: FOSTER Well #: 2  
County: SHERIDAN Total Vertical Depth: 4166 feet

Operator License No.: 30076  
Op Name: ANDERSON, ANDY DBA A & A PRODU  
Address: PO BOX 100  
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.875	4166		150 SX
SURF	8.875	255		150 SX
T1	2.375	4105		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/27/2012 10:30 AM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
8 5/8" surface casing set at 255' w/150 sx cement. 4 1/2" production casing set at 4166' w/150 sx cement. Port Collar set at 2327' was not cemented. TD 4166'. Perforations: 3844' - 3848', 4101' - 4105' and 4111' - 4115'. Well non-commercial.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/27/2012 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Sanded perforations off and dumped 5 sx cement with dump baler.  
Cut casing at 2362'. Casing cut but not free. Connected to 4 1/2" casing and pumped 125 sx cement and displaced to 1500'. Cut casing at 1500'. Pipe free. Pulled to 1380'. Connected to 4 1/2" production casing and pumped 80 sx cement w/200 # hulls.  
Pulled casing to 275' and pumped 90 sx cement. 8 5/8" surface casing full.

GPS: 39.25215N -100.22746W

Perfs:

Top	Bot	Thru	Comments
4111	4115		
4101	4105		
3844	3848		

Remarks: SOS TICKET # 648

Plugged through: CSG

District: 04

Signed Darrel Dipman  
12/4/12 (TECHNICIAN) CM

RECEIVED  
DEC 10 2012  
KCC WICHITA

NOV 28 2012