

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21624-00-00  
Spot: W2SEWNW Sec/Twnshp/Rge: 29-24S-13W  
4290 feet from S Section Line, 1765 feet from E Section Line  
Lease Name: VEDDER TRUST Well #: 1  
County: STAFFORD Total Vertical Depth: 4215 feet

Operator License No.: 3493  
Op Name: FISHER, REGINALD D.  
Address: 110 N EXCHANGE ST  
SAINT JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4214	1687	WITH 250 SX CMT
SURF	8.625	395		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2012 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SAND TO 3866' & 4 SX CMT. PLUG AT 810' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 11/19/2012 9:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SANDED TO 3850' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 810' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 100 SX CMT. FILLED CELLAR WITH CMT.

Remarks: USED 60/40 POZMIX 4% GEL.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
12/10/12 (TECHNICIAN)

RECEIVED  
NOV 29 2012  
KCC DODGE CITY

RECEIVED  
DEC 03 2012  
KCC WICHITA