

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23016-00-00
Spot: NESWNE Sec/Twnshp/Rge: 25-32S-4E
4546 feet from S Section Line, 958 feet from E Section Line
Lease Name: GANN Well #: 6
County: COWLEY Total Vertical Depth: 2454 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	200		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2012 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.
Proposal Rcvd. from: ALBERT COOPER Company: ALBERT COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND BACK @ 2250 W/5 SXS, CUT CSG, CIRC 250'-0

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/05/2012 10:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE TAGGED BOTTOM @ 2340'. 11-2-2012, SANDED WELL BACK @ 2280, DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED BOTTOM PLUG @ 2236'. 11-5-2012, SHOT SQUEEZE HOLES (2 HOLES) @ 250'-250'-1/2". RIH W/TBG @ 260', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 131 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED ON BOTH STRINGS. PLUG DOWN 10:30 AM 11-5-2012. COPELAND ACID CEMENT TICKET #38117. 11-9-2012, TAGGED CEMENT @ 19', TOPPED WELL BACK TO SURFACE W/10 SXS.

Perfs:

Top	Bot	Thru	Comments
2346	2352		CSG


RECEIVED
DEC 04 2012
KCC WICHITA

Remarks: COMPLIANCE/ COMPLAINT

Plugged through: TBG

District: 02

Signed


12/02/12 (TECHNICIAN)