

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-24108-00701 0001  
Spot: N2N2SENE Sec/Twnshp/Rge: 25-32S-4E  
3715 feet from S Section Line, 660 feet from E Section Line  
Lease Name: GANN Well #: GDO 1  
County: COWLEY Total Vertical Depth: 1947 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1930		0 SX
SURF	8.625	200		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: ALBERT COOPER Company: ALBERT COOPER/COOPER SERVIC Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS / 35 SXS @ 1636', CIRC 250'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/05/2012 2:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG & BIT CIRCULATING VARIOUS BRIDGES @ 1636', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 1320'. 11-5-2012, SHOT SQUEEZE HOLES (2 HOLES) @ 250'-250'-1/2". RIH W/TBG @ 260', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED ON BOTH STRINGS. PLUG DOWN 2:15 PM 11-5-2012. COPELAND ACID CEMENT TICKET #38118. 11-9-2012, TAGGED CEMENT @ 15', TOPPED WELL BACK TO SURFACE W/10 SXS.

Perfs:

Top	Bot	Thru	Comments
1808	1812		CSG


RECEIVED  
DEC 04 2012  
KCC WICHITA

Remarks: COMPLIANCE /COMPLAINT

Plugged through: TBG

District: 02

Signed

  
12/06/12 (TECHNICIAN)

✓JK