

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23513-00-00
Spot: SWNENE Sec/Twnshp/Rge: 2-33S-12W
992 feet from N Section Line, 994 feet from E Section Line
Lease Name: NE SPRINGER UNIT Well #: 1-2
County: BARBER Total Vertical Depth: 4582 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PLG	5.5	4530		
PROD	5.5	4582	3410	WITH 100 SX CMT
SURF	8.625	218		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 4330' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/15/2012 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BOTTOM TO 4318' & 5 SX CMT ON TOP WITH DUMP BAILER. AFTER CUTTING THE CASING THE WELL ATTEMPTED TO FLOW. 1ST PLUG AT 3405' WITH 50 SX CMT. 10/15/12: ENCOUNTERED CASING PLUGGED WITH CMT FROM 1700' TO 975'. GAS, OIL, & WATER TRAPPED IN JOINTS, PLUGGED WITH CMT. WHEN PIPE PULLED UP TO 975' CASING UNLOADED THE REMAINDER OF GAS, OIL, & WATER. CASING UNPLUGGED. 1ST PLUG AT 975' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4424	4428		
4392	4408		
4382	4428		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

OCT 25 2012

KCC DODGE CITY

RECEIVED
OCT 25 2012

KCC WICHITA