

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23778-00-00  
Spot: W2E2E2SE Sec/Twnshp/Rge: 1-21S-14W  
1322 feet from S Section Line, 353 feet from E Section Line  
Lease Name: MORRISON Well #: 2-1  
County: STAFFORD Total Vertical Depth: (228) feet

Operator License No.: 33993  
Op Name: QUEST ENERGY LLC  
Address: 2732 N REESE RD  
BROOKVILLE, KS 67425

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	172		

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2012 4:30 PM  
Plug Co. License No.: 33923 Plug Co. Name: PRECISION DRILLING, LLC  
Proposal Rcvd. from: GREG WHITEHAIR Company: PRECISION DRILLING, LLC Phone: (785) 625-6588

Proposed Plugging Method: COMPANY ATTEMPTED TO SET 8 5/8" SURFACE PIPE @ 215'. THE PIPE BECAME STUCK WITH 172' OF THE PIPE IN THE HOLE. COMPANY WORKED 3 DAYS TRYING TO FREE THE PIPE. PUMP DOWN 8 5/8" WITH CMT & CIRCULATE CMT TO SURFACE UP BACK SIDE. LEAVE 8 5/8" FULL OF CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/20/2012 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

COMPANY ATTEMPTED TO SET 8 5/8" SURFACE PIPE @ 215'. THE PIPE BECAME STUCK WITH 172' OF THE PIPE IN THE HOLE. COMPANY WORKED 3 DAYS TRYING TO FREE THE PIPE. PUMPED DOWN 8 5/8" WITH 290 SX CMT CIRCULATING CMT TO SURFACE UP 12 1/4" HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED  
DEC 03 2012  
KCC WICHITA

District: 01

Signed Richard M. Lacey  
12/1/12 (TECHNICIAN)

RECEIVED  
NOV 29 2012  
KCC DODGE CITY