

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21047-00-00
Spot: NWSWNESE Sec/Twnshp/Rge: 8-35S-30W
1919 feet from S Section Line, 1056 feet from E Section Line
Lease Name: ADAMS Well #: 4-8
County: MEADE Total Vertical Depth: 6500 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 1601 NW EXPRESSWAY, STE 1300
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3170		
CIBP		5750		
CIBP		6200		
DVT		3183		TOC @ 2460'
PROD	5.5	6495	2200	WITH 216 SX CMT
SURF	8.625	1665		WITH 750 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/27/2012 2:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 11/28/2012 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP BOTTOM 100# HULLS & 25 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 1690' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6316	6321		
5792	5806		
5773	5776		
2936	2940		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD

Plugged through: CSG

District: 01

RECEIVED

NOV 29 2012

KCC DODGE CITY

Signed

Stephen J. Pfeifer
12/11/12
(TECHNICIAN)

RECEIVED
DEC 03 2012
KCC WICHITA