

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-10030-00-00  
Spot: N2S2SWSE Sec/Twnshp/Rge: 36-27S-35W  
638 feet from S Section Line, 1986 feet from E Section Line  
Lease Name: APPLEMAN Well #: 2  
County: GRANT Total Vertical Depth: 4760 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4210	0	WITH 100 SX CMT
SURF	8.625	649		WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2012 9:00 AM  
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC  
Proposal Rcvd. from: REGO Company: H2 PLAINS, LLC Phone: (620) 628-4466

Proposed Plugging Method: COVER PERFORATIONS WITH 10 SACKS OF SAND TO 3970 AND 5 SACKS OF CONCRETE. SET CEMENT PLUGS WITH 50 SACKS AT 1855. PERFORATE @ 700' & CIRCULATE. WITH AN ADDITIONAL 50 SACKS AVAILABLE TO CHECK THE BACK SIDE (60/40 POZ, 4% GEL AND 1/4# FLO CEL.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/16/2012 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SAND BACK TO 4010' & CAP WITH 15 SX CMT. PUMP 50 SX CMT AT 1827'. TEST CASING TO 300#. VERY SLOW LEAK. PERFORATE @ 700'. INJECTION RATE 2 1/2 BPM @ 75#. PUMP 200 SX CMT VIA 5 1/2" CASING. HAD GOOD RETURNS OUT ANNULUS FOR 2/3 OF THE JOB, LOST CIRCULATION. REGAINED CIRCULATION FOR REMAINDER OF JOB. NO CMT TO SURFACE. 10/15/12: TAG CMT IN 5 1/2" @ 48'. TAG CMT IN ANNULUS @ 48'. FILL WITH SAND TO 10' & TOP OFF CASING & ANNULUS WITH 3 SX CMT. TOP OFF ANNULUS WITH 4 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4126	4128		
4090	4092		
4046	4048		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
\_\_\_\_\_  
(TECHNICIAN)

RECEIVED  
OCT 25 2012  
KCC WICHITA

RECEIVED  
OCT 19 2012  
KCC DOORE CITY

*10/17*