

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22042-00-00
Spot: E2SWSWSW Sec/Twnshp/Rge: 36-33S-14W
335 feet from S Section Line, 4926 feet from E Section Line
Lease Name: ROTH Well #: 1
County: BARBER Total Vertical Depth: 4830 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4829	3320	WITH 150 SX CMT
SURF	8.625	1018		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/16/2012 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 30 SX CMT. PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2012 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 50 SX CMT. 1ST PLUG AT 1043' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 307' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4716	4822		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____

Stephen Pfeifer
10/16/12 (TECHNICIAN)

RECEIVED
OCT 29 2012
KCC DODGE CITY

RECEIVED
OCT 25 2012
KCC WICHITA

RMB