

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22906-00-00  
Spot: N2S2SE Sec/Twnshp/Rge: 6-32S-13W  
990 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: DUGAN TRUST B Well #: 3  
County: BARBER Total Vertical Depth: 4721 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4559	3020	WITH 200 SX CMT
SURF	10.75	268		WITH 225 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/26/2012 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 935-2534

Proposed Plugging Method: SAND BACK TO 4300' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 660' WITH 50 SX CMT. PLUG AT 300' WITH 100 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/26/2012 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4300' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 650' WITH 75 SX CMT. 2ND PLUG AT 300' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4382	4398		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed: [Signature]  
(TECHNICIAN)

RECEIVED

OCT 30 2012

KCC DOJGE CITY

RECEIVED  
NOV 09 2012  
KCC WICHITA

[Handwritten initials]