

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22867-00-00  
Spot: N2S2SWNE Sec/Twnshp/Rge: 20-31S-13W  
2130 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: HARTLEY A Well #: 1  
County: BARBER Total Vertical Depth: 4480 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3834	2400	WITH 200 SX CMT
SURF	10.75	254		WITH 220 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2012 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 3638' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 10/30/2012 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

SAND TO 3638' WITH 5 SX CMT. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT.  
2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

RECEIVED  
NOV 27 2012  
KCC WICHITA

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED

NOV 19 2012

KCC DODGE CITY