

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22884-00-00
Spot: NESESW Sec/Twnshp/Rge: 33-25S-11W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MCCARTY Well #: 5
County: STAFFORD Total Vertical Depth: 4195 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4195	2407	WITH 175 SX CMT
SURF	10.75	267		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2012 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 3975' & 5 SX CMT. PLUG AT 570' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2012 10:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 3963' & 5 SX CMT WITH DUMP BAILER. WELL UNLOADED MUD OUT OF HOLE @ 2400'. 1ST PLUG AT 610' WITH 15 SX GEL & 100 SX CMT. NO CIRCULATION. 2ND PLUG AT 305'. COULDN'T CIRCULATE. SDON & TAG 610' PLUG. 11/2/12: CHECKED FLUID LEVEL. FLUID WAS DOWN 20'. RUN TBG TO 610' & DIDN'T TAG. PUMPED 20 SX GEL & 50# HULLS. GOT CIRCULATION. MIXED 50 SX CMT & 150# HULLS. PULLED TBG TO 300' & MIXED 75 SX CMT & 50# HULLS. PULLED TBG TO 60' & MIXED 40 SX CMT. CIRCULATED TO SURFACE. HOLE STAYED FULL.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
NOV 09 2012
KCC WICHITA

District: 01

Signed Michael Maier (TECHNICIAN)
11/2/12

RECEIVED
NOV - 5 2012
KCC DODGE CITY