

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-01673-00-00
Spot: NESENW Sec/Twnshp/Rge: 4-32S-3E
3668 feet from S Section Line, 2957 feet from W Section Line
Lease Name: WILSON B Well #: 1
County: COWLEY Total Vertical Depth: 3250 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2532		
PROD	7	3009		0 SX
SURF	10.5	82		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2012 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS/SAND BACK 50' ABOVE TOP PERF, CAP W/5 SKS, CIRC. 350-0

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

MIRU, SUNFLOWER WELL SERVICE, RIH ON WIRELINE W/BAILOR @2510'.
SANDED BACK @ 2430', DUMP BAILED 5 SXS CEMENT ON TOP. RIH W 2" TBG @
350 INSIDE 7" & 3/4" TBG @ 175' INSIDE SURFACE, SWEDGED INTO 7" CASING,
CONSOLIDATED WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED
170 SXS 60/40 POZMIX 4% GEL TO SURFACE. SWEDGED INTO 3/4" TBG MIXED &
PUMPED 100 SXS 60/40 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG
DOWN 12:25 11-28-2012.

Perfs:

Top	Bot	Thru	Comments
2484	2490	CSG	

Remarks: CONSOLIDATED CEMENT TICKET #35423.

Plugged through: TBG

RECEIVED
DEC 04 2012
KCC WICHITA

District: 02

Signed  (TECHNICIAN)
12/06/12