

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-01674-00-00
Spot: NWSEW Sec/Twnshp/Rge: 4-32S-3E
3723 feet from S Section Line, 3609 feet from E Section Line
Lease Name: WILSON B Well #: 2
County: COWLEY Total Vertical Depth: 3238 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3220		0 SX
SURF	13	87		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2012 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUN FLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS/ 50 SXS @ 2770', CUT CASING, SQUEEZE HOLES @ 350' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 11/16/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

MIRU SUNFLOWER WELL SERVICE, RIH ON WIRELINE W/BAILOR @ 2770'. POOH W/BAILOR. RIH W/TBG @ 2000', SDON. 11-14-2012, FINISHED RUNNING TBG @ 2750'. CONSOLIDATED WELL SERVICE ESTABLISHED CIRCULATION. MIXED & PUMPED 125 SXS CLASS A COMMON 2% CC AND DISPLACED IN CASING. LAYED DOWN TBG @ 2000'. SDON. 11-15-2012, TAGGED CEMENT @ 2260'. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 350'-351'. RIH WTBG @ 350, CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 275 SXS 60/40 POZMIX 4% GEL TO SURFACE. 11-16-2012, RIH W/ 3/4" TBG @ 350' ON SURFACE & 2" TBG @ 98' ON 7" CASING, CONSOLIDATED MIXED & PUMPED 250 SXS 60/40 POZMIX 4% CC. TO SURFACE, CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #35346.

Perfs:

Top	Bot	Thru	Comments
3220	3227	OH	

RECEIVED
DEC 04 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed [Signature]
12/06/12 (TECHNICIAN)

SK