

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-22510-00-00
Spot: NWSEWNNE Sec/Twnshp/Rge: 32-22S-13E
4429 feet from S Section Line, 1707 feet from E Section Line
Lease Name: WERNLI Well #: 4
County: GREENWOOD Total Vertical Depth: 1915 feet

Operator License No.: 5684
Op Name: SAGE, LARRY GEORGE
Address: PO BOX 12
VIRGIL, KS 66870

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	4.5	1900	1080	100 SX
SURF	8.625	102		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2012 12:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: GEORGE SAGE Company: _____ Phone: (620) 437-6103

Proposed Plugging Method: 50' cement plug @ 1850' 50' cement plug @ 1080' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2012 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1850 pumped 6 sxs. Cement, pull tubing out, shot casaing off @ 1080' pull 1 joint, pumped 2 sxs gel & pumped 10 sxs cement, pulled casing to 600' pumped 10 sxs cement pulled casing to 160' pumped 51 sxs cement to surface.pulled casing out.

Perfs:

RECEIVED
NOV 26 2012
KCC Chanute Dist. #8

mt

RECEIVED
NOV 28 2012
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed Mike Heffern
10/2/12 (TECHNICIAN)