

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10321-00-02 0002
Spot: S2S2N2NW Sec/Twnshp/Rge: 23-34S-29W
1023 feet from N Section Line, 1307 feet from W Section Line
Lease Name: ADAMS F OWWO Well #: 1
County: MEADE Total Vertical Depth: 4450 feet

Operator License No.: 30163
Op Name: GREAT PLAINS PETROLEUM, INC.
Address: 221 CIRCLE DR
WICHITA, KS 67218

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3172		
COND	13.375	35		WITH 40 SX CMT
PROD	4.5	4445	0	WITH 465 SX CMT
SURF	8.625	434		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/19/2012 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVID PAULY Company: PAULY & COMPANY Phone: (316) 264-0490

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 11/20/2012 10:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

RTIH TO 3000' & PUMP 10 SX GEL W/100# HULLS THEN 30 SX CMT W/100# HULLS 2% CC. PERFORATED AT 784'. RTIH TO 1400' & PUMPED 370 SX CMT. GOOD CIRCULATION UP 4 1/2" & 8 5/8" CASING. WATERY CMT CIRCULATED (APPROXIMATELY 5 BBLs) OUT OF SURFACE CASING. NONE CIRCULATED THROUGH PRODUCTION CASING. SDON. RTIH TAGGED CMT AT 210' & PUMPED 40 SX CMT WITH CIRCULATION. CHECKED BACKSIDE WITH 5 SX CMT & 200 PSI.

Perfs:

Top	Bot	Thru	Comments
3194	3198		
3150	3160		
3046	3050		
2989	3160		

RECEIVED
DEC 07 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
NOV 29 2012
KCC DODGE CITY

Signed [Signature]
12/10/12 (TECHNICIAN)

[Handwritten]