

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01910-00-01 0001
Spot: SESESENE Sec/Twnshp/Rge: 24-18S-8W
2964 feet from S Section Line, 310 feet from E Section Line
Lease Name: PICKERILL Well #: 4
County: RICE Total Vertical Depth: 3174 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	2894		
PROD	7	3088		250 SX
SURF	10.75	207		200 SX
T1	2.875	3150		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2012 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed SEE BELOW
Plugging
Method:

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/14/2012 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CHECK BOTTOM. SAND PERFS 50 3070' AND CAP WITH 5 SX'S CEMENT. PERORATE AT 1100', 700', & 250'. RAN TUBING TO 1100' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 700' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 250' AND ATTEMPT TO CIRCULATE CEMENT TO SURFACE. RAN OUT OF CEMENT. PULL TUBING OUT, LET SET FOR 2 HRS -- WHEN MORE CEMENT ARRIVED, PUMPED 185 MORE SX'S AND DID CIRCULATE CEMENT IN CELLAR. USED 485 SX'S CEMENT TOTAL.

Perfs:

Top	Bot	Thru	Comments
3121	3125		CSG

RECEIVED
DEC 04 2012
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #7274. COPELAND TICKET #C-41626.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
12/10/12 (TECHNICIAN)