

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21066-00-01 0801
Spot: NENW Sec/Twnshp/Rge: 5-30S-19W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: PARKIN Well #: 1-5
County: KIOWA Total Vertical Depth: 5220 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 9427 E. CROSS CREEK
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5071		WITH 2 SX CMT
PROD	4.5	5199	3157	WITH 75 SX CMT
SURF	8.625	589		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/28/2012 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5071' WITH 2 SX CMT. PLUG AT 1290' WITH 15 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2012 2:15 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5071' WITH 2 SX CMT. 1ST PLUG AT 1291' WITH 15 SX GEL & 50 SX CMT. NO CIRCULATION. PULLED UP TO 628' TRIED TO ESTABLISH CIRCULATION WITH NO SUCCESS. TAGGED CMT AT 1150'. RTIH TO 628' & PUMP 15 SX GEL, 400# HULLS, 50 SX CMT. CIRCULATION WAS ESTABLISHED. PULLED UP TO 63' & PUMPED 20 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5148	5150		
5135	5138		
5121	5125		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
NOV 29 2012
KCC DODGE CITY

Signed [Signature]
12/10/12 (TECHNICIAN)

RECEIVED
DEC 07 2012
KCC WICHITA

AWZ