

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-00116-00-01 0001
Spot: NENENW Sec/Twnshp/Rge: 10-25S-16W
381 feet from N Section Line, 2910 feet from E Section Line
Lease Name: BREITENBACH Well #: 1
County: EDWARDS Total Vertical Depth: 4690 feet

Operator License No.: 32713
Op Name: SAND POINT LLC
Address: 5909 NW EXPRESSWAY, STE 490
OKLAHOMA CITY, OK 73132

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1130		
CIBP		4230		WITH 2 SX CMT
PLG	5.5	4654		
PROD	5.5	4690	0	WITH 200 SX CMT
SURF	8.625	225		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/31/2012 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 655-4494

Proposed Plugging Method: SET CIBP @ 4160' WITH 2 SX CMT. BOND LOG & DETERMINE PROCEDURE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 10/31/2012 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4230' WITH 2 SX CMT ON TOP WTH DUMP BAILER. COULDN'T LOAD HOLE TO BOND LOG. SET CIBP @ 1130'. BOND LOG SHOWED CMT FROM 702' TO 380'. PERFORATED 5 1/2" @ 1030' & 225'. RAN TBG TO 1037'. PUMPED 50 SX CMT WITH 5 1/2" CASING SHUT IN TO SQUEEZE PERFS OFF. OPENED 5 1/2" CASING UP & PUMPED AN ADDITIONAL 150 SX CMT DOWN THE TBG. CIRCULATED CMT TO SURFACE UP 5 1/2" AND 8 5/8" X 5 1/2" ANNULUS. PULLED TBG OUT & TOPPED OFF THE HOLE WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4326	4334		
4280	4284		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

NOV - 5 2012

KCC DOORSE CITY

Signed

Richard W. Lacey
12/11/12

(TECHNICIAN)

RECEIVED
NOV 09 2012
KCC WICHITA