

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-19026-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 8-17S-24W
598 feet from S Section Line, 1981 feet from W Section Line
Lease Name: TILLEY Well #: 2
County: NESS Total Vertical Depth: 4461 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|--------------------------|
| CIBP | | 4300 | | |
| DVT | | 1571 | | CEMENTED WITH 329 SX CMT |
| PROD | 5.5 | 4451 | 0 | WITH 100 SX CMT |
| SURF | 8.625 | 53 | | WITH 40 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2012 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA Phone: (316) 265-3000

Proposed Plugging Method: SET CIBP ON BOTTOM & 2 SX CMT. RUN TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2012 4:20 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4300'. RUN TBG TO 4270' & SPOT 15 SX CMT. PULL TBG TO 1600' & PUMP 170 SX CMT. CMT CIRCULATED. PULL TBG & TOP OFF WITH 15 SX CMT. TIE ONTO BACKSIDE & PUMP 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4451 | 4461 | | |
| 4344 | 4346 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
NOV 09 2012
KCC WICHITA

District: 01

RECEIVED

NOV - 2012

KCC DOCKLAND CITY

Signed

Michael Maier
11/29/12 (TECHNICIAN)

Maier