

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-10067-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 20-22S-41W
3587 feet from S Section Line, 3114 feet from E Section Line
Lease Name: HCU Well #: 2021
County: HAMILTON Total Vertical Depth: 2678 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2677	0	
SURF	10.75	150		WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/13/2012 11:30 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 200# HULLS & 175 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2012 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2662' TO 0' USING 190 SX CMT & 150# HULLS. PRESSURE TO 400#. HOLDING AT 100#. THE ANNULUS WAS CEMENTED TO SURFACE IN 7/64 WHEN THE PIGGY BACK DISPOSAL STRING WAS CEMENTED IN. THE DISPOSAL STRING WAS PLUGGED 5/25/88.

Perfs:

Top	Bot	Thru	Comments
2654	2662		

RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
NOV 20 2012

KCC DODGE CITY

PAW