

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20455-00-01 0001  
Spot: SE Sec/Twnshp/Rge: 9-23S-41W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: HCU Well #: 0931-B  
County: HAMILTON Total Vertical Depth: 2657 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2614		
PROD	4.5	2656	0	WITH 825 SX CMT
SURF	8.625	351		WITH 230 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2012 4:00 PM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 200# HULLS & 250 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT FOR ANNULUS

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/06/2012 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2530' TO 0' USING 175 SX CMT & 150# HULLS. PRESSURE TO 500#. HOLDING AT 300#. PUMP 25 SX CMT DOWN ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2518	2530		

RECEIVED  
NOV 27 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed Ken Jehlik (TECHNICIAN)

RECEIVED

NOV - 9 2012

KCC DODGE CITY

BAWY