

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20659-00-00  
Spot: NWNWSESE Sec/Twnshp/Rge: 25-21S-41W  
1273 feet from S Section Line, 1279 feet from E Section Line  
Lease Name: HCU Well #: 2511-B  
County: HAMILTON Total Vertical Depth: 2975 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2929		
PROD	4.5	2972	0	WITH 470 SX CMT
SURF	8.625	230		WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2012 1:00 PM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 300# HULLS & 190 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT EXTRA FOR ANNULUS

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/06/2012 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2896' TO 0' USING 220 SX CMT & 300# HULLS. PRESSURE TO 600#. HOLDING AT 400#. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2838	2896		

RECEIVED  
NOV 27 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

RECEIVED

NOV - 8 2012

KCC DOC

Signed

Ken Jehlik  
11/28/12  
(TECHNICIAN)

Handwritten initials