

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20223-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 26-21S-41W
3302 feet from S Section Line, 2005 feet from E Section Line
Lease Name: HCU Well #: 2611-B
County: HAMILTON Total Vertical Depth: 2850 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2847	0	WITH 400 SX CMT
SURF	8.625	226		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/12/2012 7:30 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVET Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 200# HULLS & 175 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT FOR ANNULUS

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2012 9:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2776' TO 0' USING 195 SX CMT & 150# HULLS. PRESSURE TO 500#. HOLDING AT 350#. PUMP 30 SX CMT DOWN THE ANNULUS TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2766	2776		

RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed _____

Ken Jehlik
11/28/12 (TECHNICIAN)

RECEIVED

NOV 20 2012

KCC DODGE CITY