

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20770-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 32-21S-41W
4027 feet from S Section Line, 4044 feet from E Section Line
Lease Name: HCU Well #: 3211-C
County: HAMILTON Total Vertical Depth: 2929 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2924	0	WITH 550 SX CMT
SURF	8.625	314		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/12/2012 10:30 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVET Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 200# HULLS & 175 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2012 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2776' TO 0' USING 215 SX CMT & 200# HULLS. PRESSURE TO 500#. HOLDING AT 300#. RAN 1" DOWN ANNULUS & STACKED OUT @ 60'. CIRCULATE CMT TO SURFACE WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2756	2776		


RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BU CONSOLIDATED.

Plugged through: CSG

District: 01

Signed


11/20/12 (TECHNICIAN)

RECEIVED

NOV 20 2012

KCC DODGE CITY

ADVT