

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20767-00-00
Spot: SWSWNENE Sec/Twnshp/Rge: 36-23S-41W
4019 feet from S Section Line, 1259 feet from E Section Line
Lease Name: HCU Well #: 3631-C
County: HAMILTON Total Vertical Depth: 2570 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2565	0	WITH 550 SX CMT
SURF	8.625	311		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/05/2012 11:00 AM

Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.

Proposal Rcvd. from: KENNETH KIVET Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 250# HULLS & 160 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT EXTRA FOR ANNULUS

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/05/2012 1:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2459' TO 0' WITH 180 SX CMT & 150# HULLS. PRESSURE TO 300#. HOLDING AT 250#. PUMP 5 SX CMT DOWN ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2440	2459		


RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
NOV - 9 2012
KCC DODD CITY

19114