

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25503-00-00
Spot: NESENEW Sec/Twnshp/Rge: 30-14S-20W
720 feet from N Section Line, 2540 feet from W Section Line
Lease Name: ADDIE Well #: 30-2
County: ELLIS Total Vertical Depth: 3975 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3972		150 SX CMT.
SURF	8.625	219		160 SX CMT.
T1	2.875	3875		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2012 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MIKE STANTON Company: IA OPERATING INC. Phone: (785) 689-8633

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 16 sx gel.
Port Collar at 1542' w/165 sx cement.
Fluids: 3200'
Perforations at 3840' - 3846' and 3548' - 3553'-C

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2012 10:10 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to casing and pumped 50 sx cement w/250 # hulls followed by 16 sx gel followed by 150 sx cement w/300 # hulls. Pressured casing to 200 psi. Shut in pressure 200 psi. Took bullplug off 8 5/8" casing. Back side full of cement.

GPS: 38.81046 -099.58726

Perfs:

Top	Bot	Thru	Comments
3882	3888		
3840	3846		
3590	3595		
3548	3553		

RECEIVED
NOV 13 2012
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING INC TICKET # 6088

Plugged through: CSG

District: 04

Signed *Pat Staab*
11/06/12 (TECHNICIAN)