

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23471-00-00  
Spot: W2E2E2NE Sec/Twnshp/Rge: 5-15S-13W  
1320 feet from N Section Line, 340 feet from E Section Line  
Lease Name: GROSS Well #: 6  
County: RUSSELL Total Vertical Depth: 3210 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 83RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3175		225 SX
SURF	8.625	476		225 SX
T1	2.875	3150		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2012 12:30 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JIM Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/ 500 # hulls.  
Sanded off bottom and spotted 5 sx cement on top. Cut off casing @ 1498' leaving 1677' of 5 1/2" casing in hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2012 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing @ 1498', pulled sub out and pumped 125 sx cement w/300 # hulls.  
Pulled casing to 700' and pumped 40 sx cement w/100 # hulls.  
Pulled casing to 500' and pumped 50 sx cement w/100 # hulls.  
Pulled casing to 250' and pumped 55 sx cement. Cement circulated in cellar.  
POOH and topped off surface pipe w/25 sx cement.

GPS: 38.78032, -098.78194

Perfs:

Top	Bot	Thru	Comments
3092	3098		
3008	3014		
2994	2998		
2934	2940		

RECEIVED  
NOV 07 2012

Remarks: QUALITY CEMENTING TICKET # 6084

KCC WICHITA

Plugged through: CSG

District: 04

Signed Ray Dinkel (TECHNICIAN)

CM

NOV 02 2012