

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22394-00-00
Spot: NWSWNWSW Sec/Twnshp/Rge: 35-13S-22W
1750 feet from S Section Line, 140 feet from W Section Line
Lease Name: AMREIN FABRIZIUS UNIT Well #: 1-35
County: TREGO Total Vertical Depth: 4347 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| CIBP | | 4225 | | |
| PC | | 1798 | | 225 SX CMT. |
| PROD | 5.5 | 4347 | | 150 SX |
| SURF | 8.625 | 225 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2012 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: _____ Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-9405

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Port collar at 1798' w/225 sx cement.
Perforations: 4235' - 4239', 3958' - 3960', 3936' - 3939', 3855' - 3860' and 3816' - 3819'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2012 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3917' and pumped 10 sx gel followed by 100 sx cement w/200 # hulls.
Pulled tubing to 1910' and pumped 100 sx cement w/100 # hulls.
Pulled tubing to 911' and pumped 90 sx cement. Good circulation of cement.
Pulled tubing out of hole. Topped off with 18 sx cement. Hole standing full.
Back side is full of cement.

GPS: 38.87571 -099.74277

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4235 | 4239 | | |
| 3958 | 3960 | | |
| 3936 | 3939 | | |
| 3855 | 3860 | | |
| 3851 | 3854 | | |
| 3816 | 3819 | | |

RECEIVED
NOV 19 2012
KCC WICHITA

Remarks: ALLIED CEMENTING TICKET # 56571

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM