

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22091-00-00
Spot: NESESE Sec/Twnshp/Rge: 32-13S-21W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: LAWRENCE LOCKER Well #: 3
County: TREGO Total Vertical Depth: 4100 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4099		150 SX
SURF	8.625	207		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2012 3:00 PM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: _____ Company: STEWART WELL SERVICE INC Phone: (785) 628-8177

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Perforated from 1625' - 1626'.
Squeezed with 350 sx cement.
Perforations: 3700' - 3708', 4052' - 4058' and 4046' - 4048'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2012 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3896' and pumped 10 sx gel followed by 100 sx cement w/150 # hulls.
Pulled tubing to 1896' and pumped 100 sx cement w/150 # hulls.
Pulled tubing to 907' and pumped 72 sx cement. Good circulation of cement.
Pulled tubing out. Topped off with 12 sx cement. Hole standing full.
Back side full of cement.

GPS: 38.87353 -09967092

Perfs:

Top	Bot	Thru	Comments
4052	4058		
4046	4048		
3700	3708		
1625	1626		


RECEIVED
NOV 19 2012
KCC WICHITA

Remarks: ALLIED CEMENT TICKET # 56575

Plugged through: TBG

District: 04

Signed


11/21/12 (TECHNICIAN)

CM

NOV 15 2012