

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25450-01-00 0100
Spot: SWSESWSE Sec/Twnshp/Rge: 1-20S-25W
243 feet from S Section Line, 1905 feet from E Section Line
Lease Name: KERR 12H Well #: 1
County: NESS Total Vertical Depth: 2665 feet

Operator License No.: 34681
Op Name: ENCANA OIL & GAS (USA) INC.
Address: 5851 LEGACY CIRCLE
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	9.625	1410		WITH 620 SX CMT

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 10/31/2012 8:00 AM
Plug Co. License No.: 99994 Plug Co. Name: DOWELL SCHLUMBERGER
Proposal Rcvd. from: BRAD HUGGARD Company: ENCANA OIL & GAS Phone: (469) 865-0296

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 200 SX CMT. PULL TBG TO 1440' & SPOT 75 SX CMT. PULL TBG TO 830' & SPOT 100 SX CMT. PULL TBG TO 115' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 10/31/2012 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

****THIS WELL INTERSECTED WITH THE KERR 1H #2 AT 2500'.**** LOAD HOLE WITH DRILLING MUD. RUN TBG TO 2654' WITH 200 SX CMT. PULL TBG TO 1440' & PUMP 75 SX CMT. PULL TBG TO 830' WITH 100 SX CMT. PULL TBG TO 115' & PUMP 65 SX CMT. CMT CIRCULATED TO SURFACE.

RECEIVED
NOV 14 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SCHLUMBERGER. THIS WELL INTERSECTED WITH THE KERR 1H #2 AT 2500'.

Plugged through: DP

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED

NOV - 6 2012

KCC DODGE CITY

Form CP-2/3

AWZ