

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25499-00-00
Spot: N2SESWSE Sec/Twnshp/Rge: 24-18S-24W
345 feet from S Section Line, 1650 feet from E Section Line
Lease Name: UMMEL BROTHERS TRUST Well #: 3
County: NESS Total Vertical Depth: 2650 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 2ND AVE
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 11/04/2012 7:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: SAM Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 80 SX CMT. 3RD PLUG AT 420' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 11/04/2012 9:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

****TWISTED OFF AT 2080'. LOST COLLARS IN HOLE**** 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 80 SX CMT. 3RD PLUG AT 420' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

Stephen J. Pfeifer
11/09/12
(TECHNICIAN)

RECEIVED
NOV 09 2012
KCC WICHITA