

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20629-00-00
Spot: SENWSENE Sec/Twnshp/Rge: 4-3S-22W
1842 feet from N Section Line, 913 feet from E Section Line
Lease Name: ESSLINGER RANCH, INC. Well #: 1
County: NORTON Total Vertical Depth: 3890 feet

Operator License No.: 34494
Op Name: BECK ENERGY CORPORATION
Address: PO BOX 1070
RAVENNA, OH 44266

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 260 | | 170 sx |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/06/2012 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 230 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 12/06/2012 1:30 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st plug @3776 w/25 sx
2nd plug @2000 w/25 sx
3rd plug @1232 w/100 sx
4th plug @310 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLID

Plugged through: DP

District: 04

Signed Bruce Rodie
12/12/12 (TECHNICIAN) CM

RECEIVED
DEC 11 2012
KCC WICHITA

DEC 06 2012